

# PROGRAM REDUCTION COMPARISON

Decatur Annex Program						
Space	#	Space Category	SD GSF	VE 1-STORY GSF	Difference	Notes
TEACHING STATIONS	1	CR-01	795	795	0	7th Grade
	1	CR-02	795	795	0	8th Grade
	1	CR-03	795	0	-795	VE
	1	CR-04	838	0	-838	VE
	1	CR-05	795	0	-795	VE
	1	CR-06	795	0	-795	VE
	1	CR-07	795	0	-795	VE
	1	CR-08	795	0	-795	VE
	1	CR-09	795	0	-795	VE
	1	CR-10	838	0	-838	VE
	1	SN-01	836	795	-41	
	1	SN-02	836	0	-836	VE
	1	Science Classroom (w/ storage)	1,175	1,175	0	
	1	Dance (w/ storage)	1,734	0	-1,734	VE
	1	Art Classroom (w/ storage)	1,208	1,208	0	
	1	Kiln	202	104	-98	
ADMIN CENTER	1	Admin Office 1 (remote from office)	140	205	65	
	1	Admin Office 2 (remote from office)	136	219	83	
	1	Faculty Workroom 1 (remote from office)	436	392	-44	
	1	Faculty Workroom 2 (remote from office)	398	356	-42	
DINING & MULTI-PURPOSE	1	Student Dining Room	3,791	3,257	-534	
	1	Hybrid Kitchen (includes freezer/cooler)	1,231	1,158	-73	
	1	Servery (2 serving lines)	740	740	0	
	1	Kitchen Office	122	114	-8	
	1	Men's Kitchen Toilet	77	75	-2	
	1	Women's Kitchen Toilet	77	75	-2	
	1	Kitchen Staff Lockers	0	192	192	In Kitchen, 12 lockers
	1	Recycling	0	0	0	Included in Dining Rm
	1	Kitchen Storage	353	235	-118	
	1	Dining Room Storage (Table)	473	410	-63	(15)10'L folding tables @12p ea.
SPECIAL AREAS	1	Library	1,987	2,019	32	
	1	Gymnasium (0.75 x standard)	5,300	5,345	45	
	1	Gym Office	136	168	32	
	1	Gym Storage	920	313	-607	Includes Chair Storage
	1	Stage Storage	451	192	-259	
	1	Stage (.35 x standard)	1,545	1,370	-175	
	1	General Building Storage 1	409	298	-111	
	1	General Building Storage 2	212	298	86	
BUILDING SUPPORT	1	Main Entrance Vestibule / Annex Link	869	869	0	Includes 4-hr Vestibule
	1	All Other Vestibules	455	250	-205	East Vestibule
	1	Elevator 1st Floor	129	0	-129	VE
	1	Elevator 2nd Floor	129	0	-129	VE
	1	Elevator Machine Room	129	0	-129	VE
	1	1st Floor Corridor w/Lockers	4,724	4,219	-505	Includes Kitchen corridor
	1	2nd Floor Corridor w/Lockers	3,778	0	-3,778	VE
	1	Toilet Room 1 (Boys, Girls, Staff/Unisex & Jan.)	854	854	0	
	1	Toilet Room 2 (Boys, Girls, Staff/Unisex & Jan.)	819	0	-819	VE
	1	Stair 1 @1st	431	0	-431	VE
	1	Stair 1 @2nd	431	0	-431	VE
	1	Stair 2 @1st	514	0	-514	VE
	1	Stair 2 @2nd	649	0	-649	VE
	1	Stair 3 @1st	420	0	-420	VE
	1	Stair 3 @2nd	490	0	-490	VE
	1	Stair 4 @1st	413	0	-413	VE
	1	Stair 4 @2nd	430	0	-430	VE
	1	Chair Storage	0	0	0	Included in Gym Storage
	1	Mechanical Room	1,451	825	-626	
	1	MDF	253	259	6	IDF
	1	Electrical Room	361	310	-51	
	1	Water Room (Sprinkler Pump)	246	230	-16	
	1	Engineer's Office	136	178	42	
	1	Engineer's / Building Operations Storage	285	422	137	
Program Total			51,357	94%	30,719	90%
					-20,638	

<b>Envelope, Partition &amp; Shafts</b>	3,368	6%	3,368	10%
<b>Total:</b>	54,725		34,087	
Planned Annex GSF Area 1st flr.:	26,413		30,893	
Planned Annex GSF Area 2nd flr.:	26,421		0	
Total GSF Program vs Concept Plan:	52,834		30,893	-23,832