




U:\Cad\_Drive\_New\City of Chicago - Fleet Management\JPSTC\JPSTC\_Sample Locations.dwg



NOTES

1. THIS DRAWING IS ONLY FOR ENVIRONMENTAL SITE WORK (ILLUSTRATION PURPOSES ONLY.) CONTRACTOR SHALL REFER TO ARCHITECT/ENGINEER DRAWINGS FOR CONSTRUCTION DETAILS AND DIMENSIONS. REFER TO SITE SURVEY FOR EXISTING SURFACE ELEVATIONS.
2. THE CONTRACTOR SHALL PREPARE A SITE SPECIFIC HEALTH AND SAFETY PLAN AND PERFORM ALL WORK IN ACCORDANCE WITH ALL APPLICABLE OSHA REGULATIONS. NOTE THAT SOIL EXCEEDING THE ILLINOIS CONSTRUCTION WORKER INHALATION EXPOSURE ROUTE REMEDIATION OBJECTIVE MAY BE PRESENT AT THS SITE, AS SHOWN ON THE DRAWING.
3. ALL EXCAVATION, TRANSPORTATION AND DISPOSAL OF SOIL/FILL SHALL BE PERFORMED IN ACCORDANCE WITH SPECIFICATION SECTION 31 23 18.13. ANY SOIL OR FILL EXCAVATED FROM THE SITE AND TRANSPORTED OFFSITE FOR DISPOSAL SHOULD BE TREATED AS SPECIAL OR CERTIFIED-NON SPECIAL WASTE AND DISPOSED AT A LICENSED SUBTITLE D LANDFILL ACCORDINGLY. UNLESS POST EXCAVATION STOCKPILE SAMPLING IDENTIFIES A DISCRETE VOLUME OF SOIL THAT MEETS THE MACS AND IS ACCEPTED BY A CCDD FACILITY, IN WHICH CASE EXCAVATION, TRANSPORTATION AND DISPOSAL OF SOIL/FILL SHALL BE PERFORMED IN ACCORDANCE WITH SPECIFICATION SECTION 31 23 18.14.
4. IF ANY MATERIAL WILL BE REMOVED FROM THIS SITE FOR DISPOSAL, CONTRACTOR SHALL PROVIDE THE NAME AND ADDRESS OF SELECTED HAULERS, RECYCLING FACILITY, AND ACTIVE PERMITTED SUBTITLE D LANDFILL PER SPECIFICATION SECTION 31 23 18.13 PRIOR TO THE START OF CONTRACTOR WORK.
5. ALL FIELD EQUIPMENT SHALL BE DECONTAMINATED PRIOR TO BEING TAKEN OFFSITE.
6. ALL IMPORTED FILL MATERIALS MUST MEET THE REQUIREMENTS OF SPECIFICATION SECTION 31 23 25.
7. EXCAVATED SOIL MAY BE REUSED AS FILL WITHIN THE SITE LIMITS .
8. SHOULD ANY SOILS OR FILL BE ENCOUNTERED THAT EXHIBIT UNUSUAL OR PETROLEUM/SOLVENT ODORS OR STAINING, CONTRACTOR SHALL STOP WORK IN THAT AREA AND NOTIFY THE ENVIRONMENTAL CONSULTANT IMMEDIATELY. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE CONSULTANT IF ANY MATERIALS (SOIL OR LIQUID) REQUIRING SPECIAL HANDLING (I.E. STAINED SOIL, SOIL WITH ODORS, OR LIQUIDS) IS ENCOUNTERED DURING EXCAVATION
9. NO SOIL SHALL BE EXPORTED OR IMPORTED FROM THE SITE WITHOUT THE PRESENCE OF THE ENVIRONMENTAL CONSULTANT. NOTIFY THE CONSULTANT AT LEAST 48 HOURS IN ADVANCE FOR FIELD OVERSIGHT.
10. SHOULD AN UNDERGROUND STORAGE TANK (UST) BE ENCOUNTERED IN THE WORK AREA, CONTRACTOR SHALL STOP WORK AND NOTIFY THE EC IMMEDIATELY IN ACCORDANCE WITH SPECIFICATION SECTION 02 65 00.
11. ALL IMPORTED BACKFILL USED FOR THE PROJECT SHALL NOT EXCEED TIERED APPROACH TO CORRECTIVE ACTION OBJECTIVES (TACO): 35 ILLINOIS ADMINISTRATIVE CODE (ILL. ADM. CODE) 742 APPENDIX B, TABLE A VALUES FOR 35 ILL. ADM. CODE 740 APPENDIX A TARGET COMPOUND LIST (TCL) PARAMETERS.
12. BUILDING DEBRIS MAY BE ENCOUNTERED. SHOULD ANY SUSPECT ASBESTOS MATERIAL BE ENCOUNTERED, CONTRACTOR SHALL STOP WORK IN THE AREA OF SUSPECT MATERIAL AND IMMEDIATELY NOTIFY THE EC.
13. LEAD-BASED PAINT MAY BE PRESENT AT THE PROPERTY. IT IS RESPONSIBILITY OF THE CONTRACTOR TO TAKE APPROPRIATE SAFETY MEASURES IN ACCORDANCE WITH APPLICABLE LOCAL, STATE AND FEDERAL RULES AND REGULATIONS INCLUDING OSHA (1962.62) COMPLIANCE WASTE CHARACTERIZATION, AND WASTE DISPOSAL.
14. EXCAVATED MATERIAL ASSOCIATED WITH SAMPLE LOCATION GP-7D [BLUE SHADED AREA] WILL BE SEGREGATED FROM ALL OTHER MATERIAL AND THEN PLACED UNDERNEATH THE END USER PARKING AREA WHICH WILL PROVIDE A SOLID CAP. MATERIAL SHOULD BE SEGREGATED, WITH PHOTOGRAPHIC DOCUMENTATION RECORDING THE STEPS, AND THEN PLACED UNDERNEATH THE END USER PARKING. THE CONTRACTOR WILL BE REQUIRED TO RECORD WHERE THIS MATERIAL IS BEING PLACED, COORDINATE POINTS AND ELEVATIONS.

LEGEND

-  SOIL SAMPLE LOCATION WITH CONSTRUCTION WORKER INHALATION EXCEEDANCE FOR ELEMENTAL MERCURY
-  SOIL (2-10 FEET BELOW GRADE SURFACE) REQUIRING SEGREGATION AND USE BENEATH AN ENGINEERED BARRIER



PROJECT

JOINT PUBLIC SAFETY  
TRAINING CAMPUS (JPSTC)

JPSTC  
4434 W CHICAGO AVENUE  
CHICAGO, IL 60631

CLIENT

CITY OF CHICAGO ASSETS,  
INFORMATION & SERVICES

30 NORTH LASALLE STREET

CONSULTANT

AECOM  
303 SOUTH WACKER  
CHICAGO, IL 60601  
312-373-7700 tel 312-373-6800 fax  
www.aecom.com

CONSULTANTS

TRAINING CONSULTANT  
**ABERCROMBIE DESIGN + PLANNING**  
3508 OVERTON PARK DRIVE W  
FORT WORTH, TX 76109  
817-920-9198 tel  
http://abercrombiedesign.com/

ARCHITECTURE - INTERIOR  
**ARCHITRAVE LIMITED**  
211 W WACKER  
CHICAGO, IL 60606  
312-642-2600 tel 312-642-6916 fax  
https://www.architraveltd.com/


CIVIL ENGINEERING  
**INFRASTRUCTURE ENGINEERING**  
1 SOUTH WACKER DRIVE, SUITE 2650  
CHICAGO, IL 60606  
312-425-9560 tel 312-425-9564 fax  
https://www.infrastructure-eng.com/

LANDSCAPE ARCHITECTURE  
**JACOBS RYAN ASSOCIATES**  
1527 N SANDBURG TERRACE  
CHICAGO, IL 60610  
312-664-3217 tel 312-337-1550 fax  
http://www.jacobsryan.com/

LOW VOLTAGE  
**LEVEL-1) GLOBAL SOLUTIONS, LLC**  
233 S WACKER DRIVE, 84TH FLOOR  
CHICAGO, IL 60606  
312-202-3900 tel 312-202-3310 fax  
https://www.level-1.com/

REGISTRATION

NOT FOR CONSTRUCTION



PROJECT NUMBER

60593746

SHEET TITLE

SOIL MANAGEMENT  
PLAN

SHEET NUMBER

SM-100